

SCHEDULES

BEAM (B) SCHEDULE			
MARK	SIZE	CAMBER	REMARKS
B1	5 1/2"x24" 6LB	C=STD.	---
B2	5 1/2"x36" 6LB	C=1/4"	---
B3	3-2x8	---	---
B4	5 1/2"x16 1/2" 6LB	C=1/2"	---
B5	5 1/2"x15" 6LB	C=0	---

SHEAR WALL SCHEDULE		
MARK	MATERIAL AND ATTACHMENT	SILL PLATE ATTACHMENT 1) PLATE TO CONCRETE AT EXTERIOR WALL
SW1	15/32" PLYWOOD SHEATHING W/ 10d NAILS AT 6" O.C. EDGES & 10d AT 12" O.C. FIELD EXTERIOR SIDE (TYPICAL UNO.)	1/2" ANCHOR BOLTS AT 32" O.C.
SW2	15/32" PLYWOOD SHEATHING BLOCKED W/ 10d NAILS AT 4" O.C. EDGES & 10d AT 12" O.C. FIELD EXTERIOR SIDE (TYP. UNO.)	1/2" ANCHOR BOLTS AT 16" O.C.

SHEAR WALL NOTES:

- ALL PANEL EDGES SHALL BE BACKED WITH MINIMUM 2 INCH NOMINAL FRAMING.
- WHERE PLYWOOD IS APPLIED ON BOTH FACES OF WALL AND NAIL SPACING IS LESS THAN 6" O.C., PANEL JOINTS SHALL BE OFFSET TO FALL ON DIFFERENT FRAMING MEMBERS.
- BLOCKING SHALL BE PROVIDED NEAR MID-HEIGHT OF WALL AT SHEATHING JOINT.
- SPACING APPLIES TO NAILING AT ALL STUDS, TOP AND BOTTOM PLATES AND BLOCKING.
- SEE ARCHITECTURAL DRAWINGS FOR ADDITIONAL (FINISHED SURFACE) WALL COVERINGS NOT NOTED.
- ALL PANEL EDGES SHALL BE BACKED WITH MINIMUM 2 INCH NOMINAL FRAMING.
- PLYWOOD SHEAR PANELS MAY BE APPLIED ON THE EXTERIOR OR INTERIOR FACE OF STUDS AS REQUIRED FOR CONSTRUCTION EASE AND APPROVED BY GENERAL CONTRACTOR. COORDINATE WITH OTHER TRADES AS REQUIRED.

HOLDOWN SCHEDULE (POST SIZE 2 - 2x MINIMUM UNO.)							
MARK	SIMPSON HOLDOWN	POST SIZE	POST ATTACHMENT	BOLT TO FOUNDATION	ALL THREAD EPOXY EMBED INTO FOOTING	SIMPSON FAB EMBED INTO FOOTING	NOTES
A	HD4-SDS2.5	2-2x MIN.	10 - 1/4"x2 1/2" SDS SCREWS	REFER TO DETAIL 104/S4.1	6"	6"	---
B	HD8-SDS2.5	3-2x MIN.	20 - 1/4"x2 1/2" SDS SCREWS	REFER TO DETAIL 104/S4.1	4"	4"	---
C	HD11-SDS2.5	4-2x MIN.	30 - 1/4"x2 1/2" SDS SCREWS	REFER TO DETAIL 104/S4.1	4"	4"	---

COLUMN (C) SCHEDULE			
NOTE: FOR ANCHOR BOLT PATTERN, SEE TYPICAL DETAIL.			
MARK	SIZE	BASE CONNECTION	REMARKS
C1	H55 5x5x3/8	3/4"x12"x12" STEEL BASE PLATE W/ 4 - 3/4" ANCHOR BOLTS	---
C2	H55 6x6x3/8	1"x14"x14" STEEL BASE PLATE W/ 4 - 1" ANCHOR BOLTS	---

ISOLATED FOOTING (F) SCHEDULE					
MARK	DIMENSIONS			FOOTING REINFORCING	REMARKS
	HEIGHT	WIDTH	LENGTH		
F1	1'-0"	4'-0"	4'-0"	6 #5 EACH WAY	---
F2	1'-0"	5'-0"	5'-0"	8 #5 EACH WAY	---
F3	1'-0"	6'-0"	6'-0"	10 #5 EACH WAY	---
F4	1'-6"	4'-6"	4'-6"	#5 AT 8" O.C. EACH WAY	TOP & BOTTOM

CONTINUOUS FOOTING (WF) SCHEDULE				
MARK	DIMENSIONS		FOOTING REINFORCING	REMARKS
	HEIGHT	WIDTH		
WF1	1'-0"	2'-0"	2 #5 CONT.	---
WF2	1'-6"	4'-6"	#5 AT 10" O.C. EACH WAY	TOP & BOTTOM

255 E. Arizona Blvd. Suite 100
Phoenix, AZ 85016
Phone 602.965.9200
Fax 602.965.9200
info@bakkumnoelke.com

[bn]
bakkum noelke
CONSULTING
Structural Engineers



WAW winton architects, inc.
Phoenix, AZ 85014
1435 E. Rancho Drive
(602) 230-9778
wintonarch@gmail.com

A NEW BUILDING FOR: KIWAMI ON BELL
5327 W. BELL ROAD
GLENDALE, ARIZONA 85306
LOGOS BUILDERS SOUTHWEST

job no. 24-268
drawn DTR
approved FJN
date 12/02/24

revisions

S1.5